

CASE HISTORY

Owner: Harris County Flood Control Precinct No. 4

Engineer: Pete Davies, P.E.

Location: Jones Road & FM 1960 Houston, TX

Details: Harris County Flood Control was experiencing heavy infiltration around pipe penetration in their neighborhood storm sewer system. These RCP storm lines were previously installed over 15 years prior by another contractor. Large sink holes were developing above ground and were creating houses and businesses major concern of foundation collapse.

Rehabilitation Method: Reliner MSP structural cement liner at 2-inch minimum thickness and Special Cement admixture to ensure no shrinkage and surface cracking.







BEFORE RESTORED